

Name of work:- P & F fibre sheet in Computer Engineering department at MNIT Campus Jaipur

G-Schedule

S.No	Qty	Items	Unit	Rate	Amount
1		Providing & fixing UV stabilised fiberglass reinforced plastic sheet roofing upto any pitch including fixing with polymer coated 'J' or 'L' hooks, bolts & nuts 8mm dia. G.I plain/bitumen washers complete but excluding the cost of purlins, rafters, trusses etc. The sheets shall be manufactured out of 2400 TEX panel rovigs incorporating minimum 0.3% Ultra-violet stabiliser in resin system under approximately 2400 psi and hot cured. They shall be of uniform pigmentation and thickness without air pockets and shall conform to IS 10192 and IS 12866. The sheets shall be opaque or translucent, clear or pigmented, textured or smooth as specified.			
A	50	5.0mm thick (Wt. 8.4 Kg./Mtr. Sq.)	Sqm	1872.00	93600.00
2		Dismantling roofing including ridges, hips, valleys and rafters etc. and stacking the within 50 meter lead of:			
A	50	Asbestos Sheet.	Sqm	20.00	1000.00
			<b>Total</b>		<b>94600.00</b>

say

**94600.00**

**Rs.**

EXECUTIVE ENGINEER ESTATE SECTION MNIT  
JAIPUR

I/We hereby agree to execute the work @ .....% Above/Below of Schedule 'G'

SIGNATURE OF THE CONTRACTOR WITH FULL POSTAL ADDRESS

---