

Name of work:-		Drain covering and Remaning Drain Construction work near STP plant at MNIT CAMPUS Jaipur.			
<u>G-Schedule</u>					
S.No	Qty	Items	Unit	Rate	Amount
1	116.37	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including taking out the excavated soil and depositing and refilling of jhiri with watering & ramming and disposal of surplus excavated soil as directed with in a lead of 50 meter. All kinds of soils	Cum	155.00	18037.35
2	16.2	Filling available excavated earth (excluding rock) in trenches, plinth side of foundation etc. in layers not exceeding 20 cm. in depth, consolidating each deposited layer by ramming and watering including lead up to 50 meter and with all lift.	Cum	56.00	907.20
3		Providing and laying in position cement concrete including curing, compaction etc. complete in specified grade excluding the cost of centering and shuttering - All work up to plinth level.			
A	14.85	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).	Cum	2859.00	42456.15
4		Random Rubble stone masonry for with hard stone in foundation and plinth in Cement Sand mortar above 30 CM thick wall in:			
A	48.06	Cement Mortar 1:6 (1-Cement : 6-Sand).	Cum.	2458.00	118131.48
5		Plaster on new surface on walls in cement sand mortar 1:6 including racking of joint etc. complete fine finish :			
A	162	25 mm thick	Sqm	168.00	27216.00
6		Providing and fixing stone slab covering over drains (kota/bijoliya Quarry) Having Thickness 75 mm to150 mm including filling of joints in cement mortar 1:3 with 50 mm thick cement concrete flooring in 1:2:4 mix complete with good finish as per approved drawings and specifications			

