

Name of work:- P & F False Ceiling in Badminton hall-1 at sports Complex, MNIT CAMPUS Jaipur.

G-Schedule

S.No	Qty	Items	Unit	Rate	Amount
1	277	Providing and fixing 12.5 mm thick tapered edge gypsum board conforming to IS 2095- Part I at all height false ceiling including providing and fixing of frame work made of special sections power pressed from M.S. sheet and galvanised in accordance with zinc coating of grade 350 as per IS : 277 and consisting of angle cleats of size 25mm wide x 1.6mm thick with flanges of 22mm and 37mm at 1200mm centre to centre one flange fixed to the ceiling with dash fastener 12.5mm diax40mm long with 6mm dia bolts to the angle hangers of 25x25x0.55mm of required length, and other end of angle hanger being fixed with nut and bolts to G.I. channels 45x15x0.9mm running at the rate of 1200mm centre to centre to which the ceiling section 0.5mm thick bottom wedge of 80mm with tapered flanges of 26mm each having clips of 10.5mm at 450mm centre to centre shall be fixed in a direction perpendicular to G.I. channel with connecting clips made out of 2.64mm diax230mm long G.I. wire at every junction including fixing the gypsum board with ceiling section and perimeter channels 0.5mm thick 27mm high having flanges of 20mm and 30mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450mm centre to centre with 25mm long drive-all screws @ 230mm interval including jointing and fixing to a flush finish of tapered and square edges of the board with recommended filler, jointing tapes, finisher and two coats of primer suitable for board as per manufactures specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed all complete as per	Sqm	750.00	207750
2		Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade including all scaffolding:			
A	277	New work (two or more coats) over and including scrapping and priming coat with cement primer.	Sqm	68.00	18836
		TOTAL			226586.00
					RS

EXECUTIVE ENGINEER
ESTATE SECTION MNIT
JAIPUR

I/We hereby agree to execute the work @%Above/Below of Schedule 'G'

SIGNATURE OF THE CONTRACTOR WITH FULL POSTAL ADDRESS