

Name of work:- Development of student activity Ground at MNIT CAMPUS Jaipur.

G-Schedule

S.No	Qty	Items	Unit	Rate	Amount
1	8000	Earth work in surface excavation not exceeding 30cm. in depth but exceeding 1.5 meter in width as well as 10 Sqm on plan including disposal of excavated earth up to 50 Mtr. and lift up to 1.5 Mtr. disposed soil to be levelled and neatly dressed: All kinds of soil	Sqm	32.00	256000
2		Supplying and fixing of chain link fencing with angle iron posts 50x50x6mm placed at every 3 Mtr. apart 30cm in ground embedded in cement concrete 1:3:6 (30x30x45cm) corner and every tenth post to be strutted with (50 x 50 x 6cm) angle iron provided and fixed and fitted with posts including earth work in excavation etc. complete with chain link size.			
A	649.65	50mm x 50mm x 3.15mm	Sqm.	572.00	371599.8
3	300.00	Providing and fixing steel gate, grating, and grills made of angles, tees, square bars, flats, or black pipe with holdfast and fittings complete as per design and drawing including cutting welding and fabrication with priming coat of red oxide	Kg.	87.00	26100
4	300	Extra if square, rectangular hollow tubular sections are used or grill made by flats only	Kg.	8.7	2610
5		Providing and laying in position cement concrete including curing, compaction etc. complete in specified grade excluding the cost of centering and shuttering - All work up to plinth level.			
A	149.40	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).	Cum	3002.00	448498.8
6		Fine grinded Gangsaw cut 30-35 mm thick stone flooring over 20 mm (average) thick base of cement mortar 1:4 (1 cement :4 coarse sand) jointed grey cement slurry mixed with pigment to match the shade of stone complete as per design drawing and instruction of Fl			
A	901.58	Red sand stone (Karauli stone)	Sqm	750.00	676185
7		Providing and fixing 25 mm thick Non slippery reflective type designer paving tile with metallic hardening using 2 Kg/sq.mtr made out of cement concrete of required grade, sizes of tile upto 300X300 mm Manufactured with wet cast Vibration system in two layers and laid over base of 20 mm thick cement mortar 1:4 using neat cement slurry in cluding finishing of joints etc. complete.			
A	591	Using M-30 grade cement Concrete	Sqm	1244.00	735204
8		Half brick masonry in foundation & plinth using bricks of designation 75			
A	424.8	Cement mortar 1 : 6 (1 cement : 6 coarse sand)	Sqm.	427.00	181389.6
9		Plaster on new surface on walls in cement sand mortar 1:6 including racking of joint etc. complete fine finish : 20mm thick.			
A	424.8		Sqm	158.00	67118.4
10	1200	Carriage of Earth, Sand, Lime, Morrum manure or sludge	cum	78.00	93600
		TOTAL			2858305.60
		Say			2858305.00
					RS

EXECUTIVE ENGINEER
ESTATE SECTION MNIT
JAIPUR

I/We hereby agree to execute the work @.....%Above/Below of Schedule 'G'

SIGNATURE OF THE CONTRACTOR WITH FULL POSTAL ADDRESS