

Name of work:- Metal ceiling work in PMR Lab at Electrical Department, MNIT Campus Jaipur.

G-Schedule

S.No	Qty	Items	Unit	Rate	Amount
1		Providing and fixing tiled false ceiling of approved materials of size 595X595 mm in true horizontal level suspended on inter locking metal grid of hot dipped galvanized steel sections ( galvanized @ 120 grams per sqm both side inclusive ) consisting of main "T" runner with suitably spaced joints to get required length and of size 24X38 mm made from 0.30 mm thick (minimum) sheet spaced at 1200 mm center to center and cross "T" of size 24X25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200X600 mm and secondary cross "T" of length 600 mm and size 24X25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200X600 mm panel to form grids of 600X600 mm and wall angle of size 24X24X0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/ making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 X 37 X 25 X 1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanized butterfly level clips of size 85 X 30 X 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-			
A	47.53	GI Metal Ceiling Lay in perforated Tegular edge global white	Sqm	1536.00	73006.08
		TOTAL			73006.08
		say			73006.00
					RS

EXECUTIVE ENGINEER  
ESTATE SECTION MNIT  
JAIPUR

I/We hereby agree to execute the work @ .....%Above/Below of Schedule 'G'

SIGNATURE OF THE CONTRACTOR WITH FULL POSTAL ADDRESS